

RESOLUTION FOR APPROVAL OF UTILITY PERMITS
(RESOLUTION # 61-16-17)

WHEREAS, the Statute of the State of Oklahoma [OKLA. STAT. Tit. 18, § 437.2 and 438.4 (1991) and OKLA. STAT. Tit. 10, § 1101 (1991)] provide that rural electric cooperatives, telephone cooperative organizations and public utility companies have the right to be allowed easements pertaining thereto for the purpose of erecting poles and posts, attaching equipment wires and fixtures thereto and laying lines, pipes and conduits under the surface thereof.

WHEREAS, PTCI has requested this Board's approval of placement of utility line (pole) Project for maintenance of existing line within the County right of way at the following location on 17th job. All work to be performed shall be performed and further described as follows: Start of job: 1300' W of 16th St Rd (later on then go W for approx. 436' to end of job. Start: SW4-SE4-19-3N-15ECM Finish: SW4-SE4-19-3N-15ECM

WHEREAS, petitioner must meet all requirements of the permit.

THEREFORE, BE IT RESOLVED, the Board of County Commissioners of Texas County, Oklahoma, does hereby consent to the placement of a distribution line according to the requirements as set forth in the completed Permit Application attached. With the following special instruction to be included:

All requirements of the permit must be met and it shall be tierched.

PERMIT # 61-16-17 Granted this 17th day of April 20 17.

BOARD OF COUNTY COMMISSIONERS

Ted Steed
Chairman
Mark By
Member
Jack Steen
Member



ATTEST:

Wendy Johnson
Texas County Clerk

STATE OF OKLAHOMA
TEXAS COUNTY
PUBLIC SERVICE/PIPELINE CROSSING
LINE INSTALLATION
(Revised June 2012)

We the undersigned hereby petition the TEXAS County Board of County Commissioners to grant a permit for a public service, pipeline crossing, or line installation as described below and in accordance with the provisions as listed.

PUBLIC SERVICE/PIPELINE OWNER

CONSTRUCTION COMPANY

Name PTCI

Name _____

Contact Larry Rosas

Contact _____

Address PO Box 1188

Address _____

City Guymon State OK Zip 73942

City _____ State _____ Zip _____

Phone 580-468-2160

Phone _____

TYPE OF INSTALLATION

Electric Gas Oil Water Telephone Sewer Other

The installation will be made in the following manner:

Boring Pushing Overhead Crossing Other Trenching

A permit to erect, construct and maintain a Communication Line along, upon and across the hereinafter said county highway or road for the purpose of transporting, selling, and using communications. A plat shall be attached clearly illustrating work to be performed and further described as follows: Start approx. 1,360' W of Mile 31 & Rd U intersection, then go W for approx. 436' to end of job.

LOCATION:

Start point in the SW4 Qtr. of the SE4 Qtr. of Section 19 Township 3N Range 15ECM

Crossing or parallel to county road number Parallel Mile 32 Road to the North

Ending point in the SW4 Qtr. of the SE4 Qtr. of Section 19 Township 3N Range 15ECM

PIPELINES

Size _____

Alloy/Material _____

Contents _____

Mfg. Test Pressure _____

Working Pressure _____

Max. Operating Pressure _____

ELECTRIC

Voltage _____

Conductor Size _____

Type of Structure _____

Ruling Span _____

COMMUNICATIONS

Wires/Pairs/Strands 288

Gauge _____

Cable Type Fiber

CASING

Size 1.5" SDR

Alloy/Material _____

Wall Thickness _____

If granted, this permit is subject to the following conditions, requirements, and covenants, to wit:

1. Applications for crossing permits shall be submitted to the County Clerk no later than 5 days before a meeting of the Board of County Commissioners with a check for the amount of permit made payable to the TARRANT County Commissioners. The petitioner/contractor shall contact The County Commissioners Office at the completion of crossing for an onsite inspection.

To: TARRANT County Commissioners
PO Box 197 319 N Main. St.
Guymon, OK. 73942

2. The applicant and agree to hold TARRANT County harmless for any damage or injury to persons or property caused by or resulting from the construction, maintenance, operation, or repair of the facilities on, under, or over the County right-of-way. The petitioner/contractor will be responsible for any damage resulting from deviation of the plat.
3. All crossings shall be bored on blacktop/asphalt roads. Cutting may be permitted on caliche/dirt roads, ditches, or other surfaces with approval from the Board of County Commissioners. Blasting is not permitted.
4. The petitioner/contractor shall furnish all flagmen, lights, barricades, and warning signs meeting all laws and regulations, including those in the "Manual or Uniform Traffic Control Devices" appropriate for the construction project. The petitioner/contractor agrees to keep the road open to traffic unless approved by the Board of County Commissioners. At the conclusion of such work, the right-of-way must be cleaned up and left in a presentable condition.
5. In some cases, the petitioner/contractor shall post a performance bond in an amount to be determined by the Board of County Commissioners. Necessity for such bond will be determined by the Board of County Commissioners and the bond will be held in the County Treasurers office until the right-of-way is in a presentable condition.
6. When notified to do so by the Board of County Commissioners the petitioner/contractor agrees at their expense to make all changes in the facility on County right-of-way.
7. Aerial Facilities of four feet above the traffic lanes of the road at all aerial pole line crossings shall comply with applicable safety codes and will not be less than 20 feet. All poles, posts, studs, fixtures, down guys, wires, and other appurtenances must be kept in good repair at all times and free from weeds and brush within a 5 foot area of the installation. These facilities, when paralleling the roadway, shall be single pole line construction and located within 3 feet of the fence line, if a fence exists. If no fence exists the right-of-way line shall be located by an Oklahoma Registered Surveyor at the petitioner's expense and a copy provided to the Board prior to construction. All crossings shall be as nearly perpendicular as possible. Facility shall not interfere with the natural flow line of waterways or ditch.
8. Underground Facilities- All shall be a minimum of 5 feet below the elevation of the centerline of the road, but not less than 4 feet below the bottom of the ditch. Crossings shall be encased from right-of-way line to right-of-way line and be vented off the right-of-way lines. Concrete caps 4' wide and 6" deep may be required from edge of road to fence line. Identification markers shall be installed at each right-of-way line directly above the facility. The markers must identify the owner's name, address, telephone number, size of facility, and emergency contact number in compliance with the APWA Uniform Color Code for marking. All underground electric cable crossings must be placed in a conduit

and be a minimum of 4 feet below the ditch flow lines. Conduit placed beneath a roadway must be steel, HDPE, heavy duty PVC, or fiberglass if it is designed to withstand roadway loading and is properly protected.

Conduit placed within the right-of-way may be encased with concrete if the carrier pipe material will be within the right-of-way in addition to the carrier pipe material outside the right-of-way by being of steel or ductile iron pipe with a wall thickness greater and of the same alloy. Pipe must be properly protected from corrosion.

Facilities such as water and sanitary sewer lines crossing the county right-of-way shall be encased. The Petitioner/County Commission may approve this without encasing if cast or ductile iron, HDPE or corrugated metal pipe is used. Maintenance shall be performed by a method that will not disturb the through lane or lanes with traffic. All conduit shall be sufficient to withstand roadway loadings.

- 9 All section corners and ¼ section corners shall be protected. No lines shall cross within 50 feet of a ¼ section corner or 100 feet of a bridge.
- 10 Owners of all facilities shall be responsible, at their expense, for decommissioning of sites. Roads and right-of-way shall be restored to the original condition or better.
- 11 The granting of this temporary easement does not take into consideration whether or not the adjoining property owner is entitled to compensation for the easement being placed in the county road right-of-way.
- 12 Above ground water line running parallel with road shall be placed within 3 feet of fence line as not to disrupt road maintenance. Any line interfering with road maintenance equipment will be removed.

Schedule of Fees


Road Bored	\$500.00
Cut or Trenched	\$5000.00
Overhead Lines	\$500.00

*If the applicant for county right-of-way of board a utility permit, there shall be a fine of \$10,000.00 plus court fees.

Ag Permit

When Bored for all Water or Low Pressure Gas Line	\$25.00
When Bored for a Telephone Line	\$50.00
For Overhead Electric Lines	\$50.00

I hereby attest to the accuracy of the information contained on this application. I further certify that, in my professional opinion, the facility line as installed, the drawings, plans and specifications therefore comply in all respects with the requirements of said permit.


 _____ 4-10-17 _____ 580-468-2160 _____
 Petitioner/Contractor Signature Date Phone#

 Field Engineer

 Title

Permit Approval

The undersigned Board of County Commissioners do hereby grant the crossing described in the supplication of [redacted] with the conditions of the application as stated herein by this reference

Approved/Disapproved on this 17th Day of April, 2017


County Dist # 2

Board of County Commissioners

[Signature]
Chairman

[Signature]
Vice-Chairman

[Signature]
Member



Attest: Wendy Johnson
County Clerk/Deputy

Dated: April 17, 2017

CERTIFICATE OF COMPLIANCE
(Utility Permit # 64-16-77)

NOTE: An officer must sign this Certificate of Compliance of your firm or a Project Director

I, the undersigned _____, do hereby certify that I am _____ (title), a person deemed qualified by the Permit Holder to inspect said _____ (title) and that I have personally inspected _____ (title) pipeline facility and all drawings, plans and specifications therefor installed by _____ (permit holder) at _____ (location). A plan shall be attached clearly illustrating work to be performed and further described as follows: Start approx. 1,360' W of Mile 31 & Rd U intersection, then go W for approx. 436' to end of job. **Start: SW4-SE4-19-3N-15ECM** **Finish: SW4-SE4-19-3N-15ECM**

I further certify that I have read the provisions of the Facility and Pipeline Utility Permit Submitted by the above Permit Holder to the Board of County Commissioners for installation of a line at the above location. I further certify that, in my professional opinion, the facility line as installed, and the drawings, plans and specifications therefore comply in all respects with the requirements of said Permit.

Signature


Title/Firm/Owner

Address

Telephone

Completion Date/Date of Inspection


SUBMIT TO BOARD OF COUNTY COMMISSIONERS AT TEXAS COUNTY COURTHOUSE, PO BOX 197, GUYMON, OKLAHOMA, 73942, WITHIN 24 HOURS OF COMPLETION OF FACILITY OR PIPELINE INSTALLATION.



Intersection of Mile 31 & Rd U
Approx. 1/4 mi. West on Rd U

SEC 19 T3N R15E6M

SEC 20 T3N R15E6M



PTCI
PO Box 1188
Guyton, OK 73942
Larry Rosas, Field Engineer
(580)468-2268
Texas County
Job# GY6659F

Drawing Not to Scale