

**STATE OF OKLAHOMA**  
**TEXAS COUNTY**  
**PUBLIC SERVICE/PIPELINE CROSSING**  
**LINE INSTALLATION**  
(Revised November 3, 2014)

We, the undersigned, hereby petition the Texas County Board of County Commissioners to grant a permit for a public service, pipeline crossing, or line installation as described below and in accordance with the provisions as listed.

**PUBLIC SERVICE/PIPELINE OWNER**

Name Panhandle Solar LLC  
Contact BJ Heath  
Address 700 Universe BLVD  
City Juno Beach State FL Zip 33408  
Phone 405-326-2154

**CONSTRUCTION COMPANY**

Name Blattner Energy  
Contact Tyler McKinney  
Address 392 county Road 50  
City Avon State MN Zip 56310  
Phone 320-356-7351

**TYPE OF INSTALLATION**

Electric ☒ Gas ☐ Oil ☐ Water ☐ Telephone ☐ Sewer ☐ Other ☐

The installation will be made in the following manner:

Boring ☐ Pushing ☐ Overhead Crossing ☒ Other ☐

A permit to erect, construct and maintain a electric line along, upon and across the hereinafter said county highway or road for the purpose of transporting, selling, and using electricity. A plat shall be attached clearly illustrating work to be performed and further described as follows:

**LOCATION:**

Start point in the SE Qtr. of the SE Qtr. of Section 1 Township 2N Range 14E  
Crossing or parallel to county road number ND 850  
Ending point in the SW Qtr. of the SW Qtr. of Section 6 Township 2N Range 15E

**PIPELINES**

Size \_\_\_\_\_  
Alloy/Material \_\_\_\_\_  
Contents \_\_\_\_\_  
Mfg. Test Pressure \_\_\_\_\_  
Working Pressure \_\_\_\_\_  
Max. Operating Pressure \_\_\_\_\_

**ELECTRIC**

Voltage 230 kV  
Conductor Size 1.345"  
Type of Structure Overhead elec  
Ruling Span 500

**COMMUNICATIONS**

Wires/Pairs/Strands \_\_\_\_\_  
Gauge \_\_\_\_\_  
Cable Type \_\_\_\_\_

**CASING**

Size \_\_\_\_\_  
Alloy/Material \_\_\_\_\_  
Wall Thickness \_\_\_\_\_

If granted, this permit is subject to the following conditions, requirements, and covenants, to wit:

- 1 Applications for road crossing must be submitted to the County Clerk no later than 5 days before a meeting of the Board of County Commissioners with a check for the amount of permit made payable to the TEXAS County Commissioners. The petitioner/contractor shall contact The County Commissioners Office at the completion of crossing for an onsite inspection.  
**To: Texas County Commissioners**  
**PO Box 197 319 N Main. St.**  
**Guymon, OK. 73942**
- 2 The applicant must agree to hold Texas County harmless for any damage or injury to persons or property caused by or resulting from the construction, maintenance, operation, or repair of the facilities on, under, or over the County right-of-way. The petitioner/contractor will be responsible for any damage resulting from deviation of the plat.
- 3 All crossings shall be bored on blacktop/asphalt roads. Cutting may be permitted on caliche/dirt roads, ditches, or other surfaces with approval from the Board of County Commissioners. Blasting is not permitted.
- 4 The petitioner/contractor shall furnish all flagmen, lights, barricades, and warning signs meeting all laws and regulations, including those in the "Manual or Uniform Traffic Control Devices" appropriate for the construction project. The petitioner/contractor agrees to keep the road open to traffic unless approved by the Board of County Commissioners. At the conclusion of such work, the right-of-way must be cleaned up and left in a presentable condition.
- 5 In some cases, the petitioner/contractor shall post a performance bond in an amount to be determined by the Board of County Commissioners. Necessity for such bond will be determined by the Board of County Commissioners and the bond will be held in the County Treasurers office until the right-of-way is in a presentable condition.
- 6 When notified to do so by the Board of County Commissioners the petitioner/contractor agrees at their expense to make all changes in the facility on County right-of-way.
- 7 Aerial Facilities-Clearance above the traffic lanes of the road at all aerial pole line crossings shall comply with applicable safety codes and will not be less than 20 feet. All poles, posts, studs, fixtures, down guys, wires, and other appurtenances must be kept in good repair at all times and free from weeds and brush within a 5 foot area of the installation. These facilities, when paralleling the roadway, shall be single pole line construction and located within 3 feet of the fence line, if a fence exists. If no fence exists the right-of-way line shall be located by an Oklahoma Registered Surveyor at the petitioner's expense and a copy provided to the Board prior to construction. All crossings shall be as nearly perpendicular as possible. Facility shall not interfere with the natural flow line of waterways or ditch.
- 8 Underground Facilities- All shall be a minimum of 5 feet below the elevation of the centerline of the road, but not less than 4 feet below the bottom of the ditch. Crossings shall be encased from right-of-way line to right-of-way line and be vented off the right-of-way lines. Concrete caps 4' wide and 6" deep may be required from edge of road to fence line. Identification markers shall be installed at each right-of-way line directly above the facility. The markers must identify the owner's name, address, telephone number, size of facility, and emergency contact number in compliance with the APWA Uniform Color Code for marking. All underground electric cable crossings must be placed in a conduit

and be a minimum of 4 feet below the ditch flow lines. Conduit placed beneath a roadway must be steel, HDPE, heavy duty PVC, or fiberglass if it is designed to withstand roadway loading and is properly protected.

Steel pipelines crossing the right-of-way may be installed without encasement if the carrier pipe material within the right-of-way is superior to the carrier pipe material outside the right-of-way by being of steel at least one grade better and of the same wall thickness, or a minimum of one wall thickness greater and of the same alloy. Pipe must be properly protected from corrosion.

Facilities such as water and sanitary sewer lines crossing the county right-of-way shall be encased. The Board of County Commissioners may approve a line without casing if cast or ductile iron, HDPE or material of equal design is used. Maintenance will be performed by a method that will not disturb the through lanes or interfere with traffic. All conduits shall be sufficient to withstand roadway loadings.

- 9 All section corners and  $\frac{1}{4}$  section corners shall be protected. No lines shall cross within 50 feet of a  $\frac{1}{4}$  section corner or 100 feet of a bridge.
- 10 Owners of all facilities shall be responsible, at their expense, for decommissioning of sites. Roads and right-of-way shall be restored to the original condition or better.
- 11 The granting of this temporary easement does not take into consideration whether or not the adjoining property owner is entitled to compensation for the easement being placed in the county road right-of-way.
- 12 Above ground water line running parallel with road shall be placed within 3 feet of fence line as not to disrupt road maintenance. Any line interfering with road maintenance equipment will be removed.
- 13 **No fees on Public Utilities** by State Law but permit must still be filed and approved.

#### Schedule of Fees


|                 |                 |
|-----------------|-----------------|
| Road Bored      | \$500.00        |
| Cut or Trenched | Up To \$5000.00 |
| Overhead Lines  | \$500.00        |

If a line is placed in county right-of-way without a utility permit, there shall be a fine of \$10,000.00 plus court fees.

#### Ag Permit Farming

|                                                   |         |
|---------------------------------------------------|---------|
| When Bored for all Water or Low Pressure Gas Line | \$25.00 |
| For Overhead Electric Lines                       | \$50.00 |

I hereby attest to the accuracy of the information contained on this application. I further certify that, in my professional opinion, the facility line as installed, the drawings, plans and specifications therefore comply in all respects with the requirements of said permit.

  
Petitioner/Contractor Signature

11-8-25  
Date

405-326-2154  
Phone#

Project manager  
Title

Permit Approval

6 Commissioners

The undersigned Board of County Commissioners do hereby grant the crossing described in the supplication herein above set forth; provided that, the same shall be subject to the terms and conditions of the application incorporated herein by this reference.

Approved/Disapproved on this 24<sup>th</sup> Day of November, 20 25

County Dist # 2

Board of County Commissioners

[Signature]  
Chairman

[Signature]  
Vice-Chairman

[Signature]  
Member



Attest: Wendy Johnson  
County Clerk/Deputy

Dated: November 24, 20 25

CERTIFICATE OF COMPLIANCE  
(Utility Permit # 46-25-24)

(Inspector)

PLEASE NOTE:

an officer must sign this Certificate of Compliance  
of your firm or a Project Director.

Inspector ↓

I, the undersigned Brian Daniel, do hereby certify that I am  
Project manager (title), a person deemed qualified by the Permit Holder to inspect said  
installation, and that I have personally inspected a utility pipeline facility and all drawings, plans and  
specifications therefore; installed by Panhandle Solar LLC (permit holder) at  
(give legal description):

gal → SE 51 T2N R14E, SWSW56 T2N R15E

I further certify that I have read the provisions of the Facility and Pipeline Utility Permit Submitted by the  
above Permit Holder to the Board of County Commissioners for installation of a line at the above location. I  
further certify that, in my professional opinion, the facility line as installed, and the drawings, plans and  
specifications therefore comply in all respects with the requirements of said Permit.

\_\_\_\_\_  
Signature

\_\_\_\_\_  
Title/Firm/Owner

\_\_\_\_\_  
Address

\_\_\_\_\_  
Telephone

\_\_\_\_\_  
Completion Date/Date of Inspection

SUBMIT TO BOARD OF COUNTY COMMISSIONERS AT TEXAS COUNTY COURTHOUSE, PO BOX  
197, GUYMON, OKLAHOMA, 73942, WITHIN 24 HOURS OF COMPLETION OF FACILITY OR  
PIPELINE INSTALLATION.

RESOLUTION FOR APPROVAL OF UTILITY PERMITS  
(RESOLUTION # 46-25-26)

WHEREAS, the Statutes of the State of Oklahoma [OKLA. STAT. Tit. 18, § 437.2 and 438.4 (1991) and OKLA STAT. Tit. 69, § 1401 (1991)] provide that rural electric cooperatives, telephone cooperative corporations and public utilities shall have the right-of-way and all easements pertaining thereto for the purpose of erecting poles and posts, attaching equipment wires and fixtures thereto and laying lines, pipes and conduits under the surface thereof.

owner↓

WHEREAS, Panhandle Solar LLC has requested this Board's approval of placement of utility lines (poles, pipelines, telecommunication lines or power lines) within the County right-of-way at the following location, to-wit:

Legal Descr. SE 1/4 T2N R14E, SW 1/4 T2N R15E

WHEREAS, petitioner must meet all requirements of the permit.

THEREFORE, BE IT RESOLVED, the Board of County Commissioners of Texas County, Oklahoma, does hereby consent to the placement of a distribution line according to the requirements as set forth in the completed Permit Application attached. With the following special instruction to be included:

All requirements of the permit must be met, and the overhead line shall be installed.

PERMIT # 46-25-26 Granted this 24th day of November 20 25

BOARD OF COUNTY COMMISSIONERS



[Signature]  
Chairman



[Signature]  
Member

[Signature]  
Member

ATTEST:

Wendy Johnson  
Texas County Clerk

**OVERHEAD ELECTRIC EXHIBIT  
PANHANDLE SOLAR, LLC  
TEXAS COUNTY, OKLAHOMA**



**LEGEND:**

|  |                            |
|--|----------------------------|
|  | OVERHEAD ELECTRIC CROSSING |
|  | EXISTING FENCE LINE        |
|  | SECTION LINE               |
|  | QUARTER SECTION LINES      |

This document is preliminary in nature and does not represent a signed and sealed document.

**WARNING**  
CONTACT "CALL OKIE" AT  
1-800-522-OKIE  
TWO WORKING DAYS  
BEFORE YOU DIG FOR ALL  
UTILITY LINE LOCATIONS  
AND INFORMATION

CookPLS National, Inc.  
13800 Wireless Way,  
Oklahoma City, OK 73134  
405-603-5511

Client: NEXTERA ENERGY RESOURCES

Date: 10/29/2025

Project: Panhandle Solar, LLC

Drafted: TF

Scale: 1" = 200'

Checked: Staff

Revision: